

**EFFICIENCY & RELIABILITY** 

Gulf Stream Heat Pumps are manufactured in the USA, and have been family-owned & operated in Florida for over 20 years!

# THE ULTIMATE WARRANTY

Gulf Stream Swimming Pool Heat Pumps are covered under the best warranty in the industry. With Gulf Stream, enjoy ten-years parts and two-years labor. See warranty for details.









#### **EFFICIENCY**

Gulf Stream is 20% more efficient than leading brands. Save \$100s in costs!

#### **LONGEVITY**

Advanced performance testing & superior components are designed to last!

#### WARRANTY

Gulf Stream's in-house service stands behind the longest & strongest warranty available in the industry.

#### RELIABILITY

The only manufacturer to completely run-test every unit produced. Testing ensures proper performance.

#### PERFORMANCE

Heat faster for less with highly-optimized and efficiency-tested Gulf Stream heaters.

#### **OUIET**

Designed with your neighbor in mind. Ultra-quiet fan & compressor used for ultra-quiet operation.

#### COMPATIBILITY

Control all Gulfstream Heaters through any automation or use the built-in display.



## **COST OF OPERATION**

**GULFSTREAM** 

\$5.60 COST PER MILLION BTUS OF HEAT

NATURAL GAS

\$27.50

**ELECTRICAL RESISTANCE** 

\$38.10

**PROPANE** 

\$40.76

\* CHART BASED ON \$3.00 PER GALLON LP GAS, \$2.20 PER THERM. OF NATURAL GAS, 13C PER KILOWATT AND A HEAT PUMP WITH C.O.P OF 6.8

### **GULFSTREAM WARRANTY**

Gulfstream provides a no-nonsense warranty. No charges for full-warranty repairs (no trip charges). Parts are warranted for 10-years from the installation date. See warranty for details.

UNIT SPEC	HE-110	HE-125	HE-150	HE-125TA HEAT/COOL	HE-150TA HEAT/COOL
BTU/COP AHRI TEST POINT (80/80/80)	115,000/6.8	125,000 / 6.6	142,000 / 6.2	118,000 / 6.2	137,000 / 6.0
MIN AMPS / MAX BREAKER	37/40	37/50	37/50	37/50	40/50
WEIGHT (SHIPPING)	215 (243)	237 (265)	239 (267)	240 (266)	243 (269)
DIMENSIONS (SHIPPING)	31x31x38 (33x31x43)	31x31x46 (33x31x50)	31x31x46 (33x31x60)	31x31x66 (33x31x50)	31x31x46 (33x31x60)

<sup>\*</sup>All units meet or exceed the AHRI Low (50/63/80) Test Point with a COP of 4.0 or higher



